

Republic of the Philippines
OVERSEAS WORKERS WELFARE ADMINISTRATION
 OWWA Center Bldg., F.B. Harrison St., Cor. 7th St., Pasay City
 Tel# 833-0113 Telefax# 833-1010

P.R. No. 2023-06-0073
 DATE: 29-Jun-23

REQUEST FOR QUOTATION / PROPOSAL


COMPANY NAME:

ADDRESS OF COMPANY:

To whom it may concern:

Please quote your lowest price/s (**taxes included**) on the lot or item/s below, subject to the General Conditions indicated herein, stating the shortest time of delivery and submit your quotation using your company letterhead or this form duly signed by your official representative to Overseas Workers Welfare Administration, Third Floor OWWA Center Building, 7th Street corner, FB Harrison, Pasay City not later than **07 July 2023, 10:00 a.m.**


MARIAN GABRIELLE F. PIZARRA
 Supply Officer


Engr. GERARDO S. GATCHALIAN
 OIC, PPMD

PROJECT TITLE/NAME: Proposal for One (1) Lot - Supply and Delivery of Various Materials for the Repair of Ceiling at OWWA Central Building					DEALER'S/SUPPLIER'S OFFER	
ITEM NO.	SPECIFICATIONS	QTY	UNIT	APPROVED BUDGET FOR CONTRACT (ABC)	UNIT COST (Vat inclusive)	TOTAL COST (Vat inclusive)
	One (1) Lot - Supply and Delivery of Various Materials for the Repair of Ceiling at OWWA Central Building			₱ 950,000.00		
1.	LED Panel Lighting Fixtures, 600mm x 600mm, recessed mounted, PSU 220V, 32-40w, Daylight	130	pcs			
2.	LED Panel Lighting Fixtures, recessed mounted, PSU 220V, 9-12w round white lid, Coolights	50	pcs			
3.	LED Panel Lighting Fixtures, 300mm x 600mm, recessed mounted, PSU 220V, 18-24 watts, Coolights	70	pcs			
4.	Tracklights, warmlight, PSU 220V, white rim	40	pcs			
5.	Tracklights bar, 6', white	20	pcs			
6.	LED Linear lighting fixture, 36-40 watts, 4ft, 220V, black finish	30	pcs			
7.	PVC Electrical Pipe, 1/2" x 10ft	50	pcs			
8.	PVC Electrical Pipe, 3/4" x 10ft	50	pcs			
9.	Utility Box, metal, HD	50	pcs			
10.	Tubular 1/2" x 2" x 20ft, Galvanized	20	pcs			
11.	Electrical Wire #2.0mm, THHN 90Deg./THWN 75Deg. 600V, stranded, 150 mtr, conductor badr soft annealed copper per ASTM B-3, class B stranding per ASTM 8 (PN 1207). Insulated lead free, flame retardant PVC per UL standard 83 jacket-clear nylon per UL standard 83 for THHN or THWN wire, flame test UL 1685. 70,000 BTU/hour flame test. Attached copy of Technical sheet. Sealed packaging with PS mark seal.	8	roll			
12.	Electrical Wire #3.5mm, THHN 90Deg./THWN 75Deg. 600V, stranded, 150 mtr, conductor badr soft annealed copper per ASTM B-3, class B stranding per ASTM 8 (PN 1207). Insulated lead free, flame retardant PVC per UL standard 83 jacket-clear nylon per UL standard 83 for THHN or THWN wire, flame test UL 1685. 70,000 BTU/hour flame test. Attached copy of Technical sheet. Sealed packaging with PS mark seal.	5	roll			
13.	PVC Laminated Ceiling Tiles, 9mm Thickness 600mm x 1200mm, Lemon Skin White	700	pcs			
14.	Main Tee Runner 12', 0.5mm Thickness	170	pcs			
15.	Cross Tee Runner 4', 0.5mm Thickness	950	pcs			
16.	Cross Tee Runner 2', 0.5mm Thickness	950	pcs			
17.	Wall Angle 12', 0.05mm Thickness, .5mm Thick	150	pcs			
18.	Thread Rod 3/8" x 3 meter	165	pcs			
19.	Hanger Clip, (related to Item 12 and Tee Runners)	350	pcs			
20.	Grip Anchor Bolt 3/8"	350	pcs			
21.	SDS-plus masonry drill bit 3/8"	10	pcs			
22.	SDS-plus masonry drill bit 1/4"	10	pcs			
23.	Drillbit 1/8", metal	10	pcs			

